South Pool (214 lineal feet) Schedule and scope of work

Quotes need to be based on total linear feet of each pool and additionally broken down on a per linear feet bases

Job description	Specifications	Job duration	Price
Plans and Permits expediting	Submitted and approved by the City of Miami & Plaza Association	3 Weeks	
Install dust barrier protection Lower the pool water lever 4"	Avoid dust and any projectiles going out of the working area or into the pool	1 Day	
Saw cut, remove and disposal the concrete	Contractor shall cut and remove cracked and delaminated concrete in damaged areas as directed. Install new expansion joint as shown	2 Weeks	
Remove and disposal of all remaining horizontal tiles	Remove both sections of the horizontal tiles. Disposal into the same dumpster	2 Days	
Install expansion join	½"-Neoprene or better. See attached spec.	2 Days	
Surface repair	Utilize Hydraulic cement for all re-setting of new tile and for all concrete repairs.	4 Days	
Pressure clean the gutter and clean the entire working area	The entire working area should be clean and ready for the next step using pressure clean and any cleaning product needed.	2 Days	
Apply water proof stucco in the gutter area	Waterproof seal all stucco joints in gutter area per attached specifications (Stucco base with Flex-Crete) or better.	3 Days	
Install new ceramic tiles on the horizontal perimeter in both sections	The tiles to be installed must match the existing ones inside the pools. The installation product must comply with attached spec (Laticrete) or better.	1 Week	
Install all new signs in the exact location	The signs must be placed in the same location and must give the same information as existing ones.	3 Hours	
Apply water proof calking around the perimeter of the pool	This water proof must comply with attached spec (NR-201) or better.	2 Days	
Final cleaning, remove the dust barrier and refilled pool water	When finish the cleaning the pool needs to be ready for reopen	1 Day	
			Tax: Included
			Profit: N/A
			Total: \$41,145.00

Warranty Information:

2 Years labor and materials.

Tile to be manufactured by Vidrepeur, supplied and installed by Greenbrook Pools.