

ROSMEL POOLS, INC.,8045 NW 36 ST SUITE 540 DORAL,FL. 33166-SALES:305.592.7900,FAX: 305.592.7997-CPC-1456804 - rosmelpools.com

MARQUIS I OF CORAL WAY - MELISSA ABRIL **Customer Name** Date 8/12/2013

Customer Address 280 SW 20th Road MIAMI FL 33129

Customer Number 305 910 4834

Customer E-Mail marquis-support@hotmail.com - eric@camassistant.com

Pool Proposed Scope of Work

RE-PLASTER PERMIT (ALLOWANCE / \$500.00)

REMOVE INTERIOR PLASTER & WATER LINE TILE TO BARE CONCRETE.

REPAIR WITH EPOXY UP TO 15' L. FEET OF STRUCTURAL CRACK ON THE INTERIOR OF SPA (ANY

ADDITIONAL LINEAL FEE WILL BE CHARGE @ \$150.00).

FILL SPA TO DO WATER TEST.

ANY LEAKS FOUND WILL HAVE TO BE INJECTED FROM OUTSIDE WITH POLYURETHANE INJECTIONS TO SEAL LEAK (\$1,500 INCLUDED ON CONTRACT).

NEW WATERPROOFING (FLEX-CRETE) WITH A 5 YEAR WARRANTY.

NEW WATER LINE TILE & MUD CAP TILES FOR STEPS.

NEW DIAMOND BRITE PLASTER (5 YEAR WARRANTY) & BENCH.

NEW MAIN DRAIN FRAME & GRATE (BY CODE).

NEW JET COVERS.

PATCH STUCCO ON THE OUTSIDE & UNDER THE SPA WHERE CRACKS ARE REPAIR (PAIN TOUCH BY BUILDING).

NEW HAND RAIL (ANCHORED TO DECK).

ELIMINATE PROTRUDING SKIMMER LED & INSTALL SPRING LOADED EQUILIZER VALVE.

NEW CHEMICAL CONTROLLER WITH FEEDERS & 2 (32 GAL) TANKS.

NEW PRESS GAUGE & FLOW METER.

NEW DISCONNECT VALVE, CHECK VALVE AND FLOW REGULATING VALVE ON SPA HEATER.

INSTALL THERMOMETER ON RECIRCULATING LINE DOWNATREAM FROM HEATER RETURN.

LEAVE AIR GAP AT SPA WASTE LINE.

PROVIDE NEW TRANSFORMER FOR LIGHT.

SITE CLEAN UP.

CHEMICAL START UP

TOTAL PRICE FOR THE SCOPE OF WORK LISTED ABOVE \$

21,450.00

NOT INCLUDED:

ITEMS ON LIST FROM DOH #1, 9a TO 12, 16, 23 7 24. THESE NEED TO BE DONE BY BUILDING.

Nos. 5, 6 & 7 REFFERING TO DECK WORK, IF IT WASN'T CORRECTED ALREADY, WE CAN GIVE A SEPARATE QUOTE TO BRING UP TO CODE.



Customer Name MARQUIS I OF CORAL WAY - MELISSA ABRIL Date 8/12/2013

Customer Address 280 SW 20th Road MIAMI FL 33129

Customer Number 305 910 4834

Customer E-Mail <u>marquis-support@hotmail.com - eric@camassistant.com</u>

PAYMENT SCHEDULE	
30% DEPOSIT	\$ 6,435.00
50% STRUCTURE REPAIR & TILE INSTALLED	\$ 10,725.00
20% WHEN JOB COMPLETED	\$ 4,290.00

ACCEPTANCE OF PROPOSAL	
THE ABOVE PRICES, SPECIFICATIONS, AND CONDITIONS ARE YOU ARE AUTHORIZED TO DO THE WORK AS SPECIFIED. PAYMENT WILL BE MADE AS OUTLINED ABOVE.	
CUSTOMER SIGNATUR <u>E</u>	CONTRACTOR SIGNATURE
DATE OF ACCEPTANCE	-